

**DPW Electrical System Upgrade
and Fire Alarm Installation
Addendum #1: August 29th, 2016**

1. Intermediate Metal Conduit (I.M.C) is the type of conduit required for fire alarm service.
2. Ground rod must be connected with #6 ground wire for the fire alarm master box.
3. A duct smoke detector and fan shut down is not needed for heating unit.
4. Service cannot be shut down during work hours. It can only be shut down after 3:30, or on a Saturday, with 48-hour advanced notice.
5. There shall be no fire alarm review fee required by the contractor.
6. U.K. listed fire alarm M.C. Cable can only be run where it can be fished concealed in walls or above ceilings.
7. The (4) rate of rise detectors in the upper unheated garage are conventional, with a monitoring module located in the adjacent heated garage.

